



## **Excavation Bid Sheet**

Green Country Habitat for Humanity (GCHFH) homes are typically built on small lots. Some of these homes are built on infill lots while others are constructed in new subdivisions. Although most lots are topographically flat, others can be a challenge meeting the required grades for proper drainage and finished floor elevations.

Each site will need assessment to determine the amounts of cut and fill to meet specific lot requirements.

The excavation contractor shall provide all labor, operations, materials, equipment necessary to complete the following:

### **Site Preparation**

- Strip native topsoil and all other organic matter within building pad and driveway areas.
- Remove and dispose of trees, stumps, shrubs, rubbish, and other unwanted materials produced by site prep.
- Deliver and place approved engineered fill-in amounts to meet required subgrade elevations.
- Ensure proper drainage of site by cut and fill operations.
- Deliver and place aggregate in prepared driveway area.

### **Finish Grade**

- After concrete slab and porches have been poured and cured, prep site to within 4" of final grade ensuring proper drainage away from building.
- At completion of concrete drives, walks and right of ways, complete finish grade with acceptable topsoil to prepare for sodding.

Please submit cost based upon man and machine hours and rates, plus quantity of materials (delivered and removed) and cost per unit required to complete project.

*Please reference which site you are bidding, include references, licenses and certifications. For more, including insurance requirements and accounts payable schedule, visit [greencountryhabitat.org/bids](http://greencountryhabitat.org/bids).*